



MINIMUM SIDEWALK WIDTHS

COMMERCIAL/INSTITUTIONAL: 8'
RESIDENTIAL: 5'

NOTES:

1. CONTRACTION JOINTS SHALL BE AS SHOWN ABOVE. EXPANSION JOINTS SHALL ALSO BE PLACED IN THE SIDEWALK SECTION AT DRIVEWAY AND ALLEY RETURNS. ALL JOINTS SHALL BE CLEAN AND EDGED WITH AN EDGE HAVING 1/4" RADIUS. JOINTS SHALL BE FLUSH WITH THE FINISHED SURFACE.
2. ALL UTILITY POLES, METER BOXES, ETC. IN SIDEWALK AREAS SHALL HAVE 3/16" EXPANSION JOINT MATERIAL (FULL DEPTH) PLACED AROUND THEM BEFORE PLACING CONCRETE.
3. PREMOLDED JOINT FILLER SHALL BE PER THE SPECIFICATIONS.
4. FORMS SHALL BE EITHER WOOD OR STEEL AND SHALL MEET ALL REQUIREMENTS OF THE SPECIFICATIONS.
5. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI @ 28 DAYS

STANDARD DETAILS	
DRAWING TITLE.	
SIDEWALK PLAN AND SECTION	
DATE:	SCALE:
AUGUST 2018	NONE
PLATE NO:	SPEC. SECT. _____
R-18	PAGE _____